

KANSAS

15-051-02114-00-00

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Sum Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name Jergensen Well No. 2

Location NEe SW Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3442'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering Co.

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12 A Day 26 Month 1 Year 1974

The above well was plugged as follows:

Total Depth 3442' 15 1/2 csg set at 93' cwc 10 3/4 csg set at 1152' cwc 625 sk.

7" csg set at 3436' Top of cement 2790'.

Set 7" wood plug at 3050' -poured 25' sand -dumped 5 sk cem W/dump bailer. (3000-3050)

Cutoff and recovered 2540' of 7" csg.

Filled 10 3/4 csg W/mud to 450' -set rock & sand bridge (450-430)

Filled with readymix cement from 430' to base of collar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/1/74

INV. NO. 8487-W