

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sun Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name Henderson Well No. 2

Location NE NE NW Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth ~~XXXX~~ 3535'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 12 N Day 15 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 3535' 16" csg 100' cwc 100 sk. 10 3/4 csg 1181' cwc 685 sk.

7" csg set at 3457' cw 200 sk cmt.

4 1/2 csg liner set (3415-3535) & cemented.

4 1/2 liner perf. (3477-3484)

Set wood plug at 3415' -poured 25' sand -dumped 5 sk cement with dump bailer.

Cutoff & recovered 2300' of 7" csg.

Filled 10 3/4 csg with mud to 420' -rock & sand bridge (420-400')

Dumped readymix cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/18/74

INV. NO. 8764-W

Signed: Leo F. Massey
Well Plugging Supervisor