

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Theodore Gore

Complete Address: 650 4th Natl Bk Bldg Wichita, Kans

Lease Name Stein Well No. 1

Location CE $\frac{1}{2}$ NE SE Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3411 3441 AUB

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 12 Day 12 Month 12 Year 63

The Above well was plugged as follows:

8 5/8" 1095' circulated with cement - 5 1/2" 3394' with 100 sax cement -

4 1/2" liner 3065' to 3441' cemented in - perf 3411'

Sanded back to 3400', set 4 sax cement with dump bailer - pulled 2800'

5 1/2" - filled hole with heavy gel mud to 500' set 20 sax cement at 500', h

heavy gel mud to 200', set 20 sax cement at 200', heavy gel mud to 35',

set bridge and 10 sax cement to bottom cellar.

Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/18/63

INV. NO. 8311-W

Signed: [Signature]
Well Plugging Supervisor