

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
OCT 11 1974  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Clinton Oil Company

Complete Address Box 1201 Wichita, Kansas 67201

Lease Name R. Stein Well No. 2

Location S/L - W/4 NW SE AUB KCC Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3471'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas License No. 683

Operation Completed: Hour 10 A Day 9 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3471' 10 3/4 csg set at 1135' cwc

7" csg set at 3400' cw 200 sk cmt.

7" csg squeezed thru Dakato Section & circulated to surface. No pipe recovered.

7" csg PBSD 1440' -dumped 5 sk cem.

Filled 7" csg W/mud to 410' -set rock & asand bridge (410-400)

Filled with readymix cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 10/11/74

INV. NO. 81-W