

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address P. O. Box 1201, Wichita, Kansas 67201

Lease Name R. Stein Well No. 5

Location C W/2 SE SE Sec. 7 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3402'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 4 Month 10 Year 1974

The above well was plugged as follows:

TD 3402' 8 5/8 csg set at 1110' cwc

7" csg set at 3400' cw 200 sk cmt.

5" liner (3326-3396) cemented.

Set 7" plug at 3326' -poured 10' sd -dumped 5 sk cmt W/dump bailer. (3326-3295)

Cutoff and recovered 2303' of 7" csg.

Filled 10 3/4 csg with mud to 410' -set rock & sand bridge (410-400)

Filled with readymix cement from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 10/8/74

INV. NO. 56-w