

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas 67202

Lease Name John Carmichael "D" Well No. 1

Location C S/2 SW SW Sec. 8 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3720'

Abandoned Oil Well Gas Well Input Well SWD Well XXX D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by Sun Cementing Co.

Address License No.

Operation Completed: Hour 6:30 P Day 23 Month 5 Year 1973

The above well was plugged as follows:

Total Depth 3720' 15" csg 67' cwc 60 sk. 10 3/4" csg 1095' cwc 500 sk.

7" csg 3366' cw 200 sk cmt.

5 1/2" liner 3320-3465 cw 25 sk cmt. No pipe recovered.

Set 107 jts tbgs at 3203.47' -circ. 35 sk gel & water -displaced 30 sk cmt.

Pulled 95 jts tbgs set at 359.66 - circ. 70 sk cmt to base of cellar.

Pulled remaining 12 jts tbgs & capped 7" csg with 15 sk cmt.

Pumped down (10 3/4-7") anulus with 10 sk gel & water & 70 sk cmt W/200 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey
Well Plugging Supervisor

INVOICED

DATE 5/31/73

INV. NO. 7423-W