

15-051-05602-00-00

KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 83-13 Location: NW NW SE

County: Ellis Sec. 8 Twp. 11 Rge. 17 (E) (W)

Name of Field or Pool: _____ Total Depth: 3490

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Day _____

Operator's Full Name Morganstern-Specter

Complete Address: Box 661 Russell, Kans

Plugging Contractor: Forbes Casing Pulling Co

Address: _____ License No. 49

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

If well is a rotary drilled dry hole did operators wait for you to arrive _____

If yes how long _____ Reason: _____

Operation Completed: Hour 12:30 PM Day 14 Month 4 Year 58

The above well was plugged as follows:

8 5/8" at 1119' circulated with 600 sax cement - 5 1/2" 3475' with 100 sax cement behind - perforated 3166'

Filled with sand to 3150', set 4 sax cement with dump bailer, pulled 2850' 5 1/2" to 500' circulated hole with heavy mud through 5 1/2" at 500'

(Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set rock

and 10 sax cement to 0'.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *Edson*
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RCW

04-18-58

Reviewed: *J. Lewis Brock*
Field Supervisor

Signed: _____
Well Plugging Supervisor

Remarks:

PLUGGING
FILE NO. 8 T 11 R 17W
BOOK PAGE 83 LINE 13