

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 83-14 Location: SE NW SE  
County: Ellis Sec. 8 Twp. 11 Rge. 17 (E) (W)  
Name of Field or Pool: \_\_\_\_\_ Total Depth: 3480

I have this date completed supervision of plugging of:

Well No. 2 Lease Day  
Operator's Full Name Morganstern & Specter  
Complete Address: Box 661 Russell, Kans  
Plugging Contractor: Forbes Casing Pulling  
Address: \_\_\_\_\_ License No. 49

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 12 Noon Day 18 Month 4 Year 58

The above well was plugged as follows:

8 5/8" 1141' circulated with cement - 5 1/2" 3479' with 100 sax cement  
behind - squeezed at 2636' with 230 sax cement - perf 3117'  
Filled with sand to 3050', set 4 sax cement with dump bailer, pulled  
1735' 5 1/2" to 500', circulated hole with heavy mud ( Gel), displaced  
20 sax cement through 5 1/4" at 500', heavy mud to 200', displaced 20 sax  
cement through 5 1/2", heavy mud to 35', set rock and 10 sax cement to 0'.  
Mudding and cementing by Forbes Co pump truck.

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: *[Signature]*  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

*[Handwritten initials]*  
*[Stamp]*  
04-25-58

Reviewed: *[Signature]*  
Field Supervisor

Signed: \_\_\_\_\_  
Well Plugging Supervisor

Remarks:

PLUGGING  
FILE SEC 8 T. 11 R. 17  
BOOK PAGE 83 LINE 14