

YD
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 11 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Lario Oil & Gas

Complete Address: 301 S Market Wichita, Kans

Lease Name Gilbert Well No. 2

Location NE SW NE Sec. 8 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3435

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith

Address: Ellinwood License No. 396

Operation Completed: Hour 7PM Day 9 Month 8 Year 64

The Above well, was plugged as follows:

8 5/8" 1118' circulated with cement - 5 1/2" 3433' with 100 sax cement

Filled with sand to 3420' - set 4 sax cement with dump bailer - pulled
2800' 5 1/2" to 700' circulated hole with heavy gel mud through 5 1/2" at
700' (20 sax Gel) - displaced 20 sax cement through 5 1/2" at 450' - heavy
mud to 200' - displaced 20 sax cement through 5 1/2" at 200', heavy mud
to 30' - cement to 30' to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edson Petty*
Well Plugging Supervisor

INVOICED

DATE 8/11/64

INV. NO. 9033-W