

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,979-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Frontier Oil Co.

Complete Address 1720 K.S.B. & T. Bldg., Wichita, Ks 67202

Lease Name Ganoung Well No. 3

Location NW SW NE Sec. 8 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3402

Abandoned Oil Well XXX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing Co. Inc.

Address Box 31, 332 W. Wichita St., Russell, Ks. 67665 License No.

Operation Completed: Hour: 2:20 PM Day: 8 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All XXX Part None

The above well was plugged as follows:

8 5/8"-1116' S.B. cuc. w/400 sacks common cement. Ordered 165 sacks 50/50 posmix
4% Gel.-3% Cal. Cl., 20 sacks Gel., 5 sacks hulls & 8 5/8" plug. Pumped into 8 5/8"
S.P. w/ pump truck, 4 sacks hulls, 25 sacks cement, 15 sacks Gel., 70 sacks cement
5 sacks Gel., 1 sack hulls, released plug & followed w/70 sacks cement.

Maximum pressure 600 pounds

Amount of Surface Casing: 1116' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

[Large handwritten signature]

Signed:
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1982
CONSERVATION DIVISION
Wichita, Kansas

7-13-82
616-W