

15-051-02132-0050

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 8 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Great Bend Pipe & Supply

Complete Address: Drawer (B) Great Bend, Kans

Lease Name Gumble Well No. 3

Location SW NW NW Sec. 8 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3416

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 10AM Day 6 Month 5 Year 64
82

The Above well, was plugged as follows:

8 5/8" 830' circulated with cment - 5 1/2" 3414' with 75 sax cement.
Holes in 5 1/2" - well sanded back naturally to 3300' - well flowing
through 5 1/2" and in 8 5/8" - 5 1/2" annulus.

Pumped 12 sax gel and 12 sax weight mud in annulus to kill water
flow in annulus - pulled 2240' 5 1/2" to 775' - circulated 18 sax gel mud
through 5 1/2" to kill flow in 5 1/2" - displaced 35 sax cement through 5 1/2"
at 475' - heavy mud to 200', displaced 25 sax cement through 5 1/2" at 200',
heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edson Peety*
Well Plugging Supervisor

INVOICED
DATE 5/8/64
INV. NO. 9112-w