

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 38-34
LOCATION SE SE NW
SEC. 8 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease Gumble

Operator Lee Phillips Oil Co Address 1407 Union Natl Bak Bldg

Field _____ County Ellis

Total Depth 3419 Feet.

Plugging Contractor R & S Pipe Pulling Co & Halliburton Cementing

Plugging Contractor's License No. 1

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 866' beirculated with cement - 5 1/2" at 3419' with 80 sax cement behind.

Filled with sand to 3400' set 4 sax cement with dump bailer,

pulled 2793' 5 1/2" - pumped hole full mud (40 sax Gel) - pumped

cementing plug to 250', followed by 80 sax cement - cement 250'

to 0'.

Mudding and cementing by Halliburton Co - 400# pump pressure.

RECEIVED
STATE CORPORATION COMMISSION

Edwin J. Perry
District Conservation Agent

Date 2-19-56

FEB 20 1956
02-20-56
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 8 TWP 11 RGE 17
BOOK PAGE 38 LINE 34