


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County, Sec. 23 Twp. 13S Rge. 11W (E) (W)
Location as "NE/CNW/SW" or footage from lines. NE SW SW
Lease Owner Sierra Petroleum Company, Inc.
Lease Name Dumler Well No. #6
Office Address c/o S.P. Hall, Box 232, Russell, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed yes 19____
Application for plugging approved yes 19____
Plugging commenced 3-19-62 19____
Plugging completed 3-22-62 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3276' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | | 2,654' |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into total depth. Sanded back to 3130'
Dumped 4 sacks of cement.

Worked & shot 5 1/2" casing free @ 2654'
Built rack & slide.

Pulled & layed down casing.

Squeezed well with 10 sacks of mud, and 80 sacks
off cement, capped well with 5 sacks of cement.

RECEIVED
MAR 29 1962
03-29-1962
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P.O. BOX 221, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes

(employee or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
J.O. Forbes
Great Bend, Kansas. (Address)

SUBSCRIBED AND SWORN TO before me this 26 day of March, 1962

My commission expires April 8, 1965

Arthur F. Hubel
Notary Public.

B & R Drilling, Inc.
Dumler #6

15-167-05804-00-00
NE SW SW of Sec. 23-13-14
Russell County, Kansas

Total Depth: 3272'
Comm. 12-18-51
Comp. 1-2-52

Casing

8 5/8" Set @ 184
5 1/2" Set @ 3272

Cement

136 Sacks Lone Star
100 Sacks Lone Star

Formation

Depth

| | |
|-----------------------|------|
| Surface Clay | 40 |
| Shale-shells | 70 |
| Shale-shells | 95 |
| Shale-sand | 105 |
| Shale-shells | 145 |
| Blue Shale | 190 |
| Shale | 210 |
| Shale-iron | 375 |
| Iron Pyrite | 385 |
| Iron | 410 |
| Iron | 425 |
| Shale-Iron | 465 |
| Shale-shells | 500 |
| Shale-Red bed | 865 |
| Anhydrite | 895 |
| Shale-shells | 1300 |
| Shale-salt | 1425 |
| Shale-shells-red rock | 1495 |
| Shale | 1515 |
| Anhydrite-shale | 1535 |
| Shale-lime | 1610 |
| Anhydrite-shaly lime | 1675 |
| Shale | 1771 |
| Lime-shale | 1865 |
| Lime | 1880 |
| Lime-shale | 2385 |
| Shale | 2484 |
| Shale-lime | 2965 |
| Lime | 3000 |
| KC Lime | 3046 |
| Lime-chert | 3091 |
| Lime | 3245 |
| Shale-lime | 3272 |

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1962
03-12-1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 11th day of January, 1952.

Notary Public

My commission expires: 6-17-54.