

Send to 5-10-61

15-167-05805-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Russell County, Sec. 23 Twp. 13S Rge. 14W (E) (W)

Location as "NE/CNW&SW" or footage from lines NW SE NW SW DNB RCL

Lease Owner Sierra Petroleum Co., Inc.

Lease Name Dumler Well No. # 7

Office Address Box 232 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed yes 19 _____

Application for plugging approved yes 19 _____


Plugging commenced 10-28-61 19 _____

Plugging completed 11-1-61 19 _____

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3282' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>5 1/2"</u>		2874' <u>2625'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging commenced 10-28-61. Plugging completed 11-1-61.

Measured in to total depth: 3282'.

Sanded back to 3270' and dumped 4 sacks cement.

Worked & shot 5 1/2" casing free at 2625'. Built rack and slide.
Pulled & layed down casing.

Squeezed the well with 80 sacks of cement.

11-06-1961
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 61

My commission expires December 8th, 1963

Kayann Jenkins
Notary Public.



15-167-05805-00-00

B & R Drilling, Inc.
Dumler #7

NW SE SW of Sec. 23-13-14
Russell County, Kansas

Total Depth: 3282'
Comm. 1/3/52
Comp. 1/14/52

Casing

8 5/8" Set @ 193
5 1/2" Set @ 3278.42

Cement

130 sax Lone Star
100 sax Lone Star

Formation

Depth

Surface clay	10
Shale-sand	190
Shale-iron-pyrite	255
Shale-iron	425
Sand-shale	464
Sand-shale	530
Shale-red bed	865
Anhydrite	900
Shale--shells	1190
Shale-salt	1300
Shale-shells-red bed	1340
Shale-lime	1875
Anhydrite-lime	1905
Lime-shale	3000
Lime	3175
Lime-shale	3278
Lime	3280
Arbuckle	3282

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 21st day of January, 1952.

Notary Public

My commission expires: 6-17--54.

10-26-1961
CONSERVATION DIVISION
Wichita, Kansas