

15-167-20546-00-00

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1975  
10-21-1975  
CONSERVATION DIVISION  
WICHITA, KANSAS  
FORM CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

WELL PLUGGING RECORD

Russel County, Sec 24 Twp 13 Rge 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner Jett Drilling Co.

Lease Name Krug Well No. 1

Office Address 514 One Twenty Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 8/8/72 19 72

Application for plugging filed 9/24/ 19 75

Application for plugging approved 9/30/ 19 75


Plugging commenced 10/10 19 75

Plugging completed 10/17 19 75

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 10/7/ 19 75

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Duane Rankin

Producing formation Arbuckle Depth to top 3288 Bottom 3292 Total Depth of Well 3292 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	263	8 5/8		
		0	3293	5 1/2		2410

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand up to 3265 Dumped 5 sx. cement on bottom

Pumped top with Allied cements 2 sx. hulls 25 sx. jell 1 sx. hulls add 200 sx. 50 50 pozmix cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Nicholas Casing Pulling

Address Box 373 Geneseo Kansas 67444


STATE OF \_\_\_\_\_ COUNTY OF \_\_\_\_\_, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Nicholas

Subscribed and sworn to before me this 20 day of October 19 75 (Address)

My commission expires August 25, 1979



Notary Public.

15-167-20546-00-00

WELL LOG

<b>Operator:</b>	Jet Drilling Company, Inc. 514 - 120 Building Wichita, Kansas 67202	<b>Description:</b>	SW-SW-SW Sec. 24-13S-14W Russell County, Kansas
<b>Name:</b>	Krug No. 1	<b>Elevation:</b>	1831' G.L. 1833' D.F. 1836' K.B.
<b>Commenced:</b>	July 4, 1972	<b>Production:</b>	Arbuckle
<b>Completed:</b>	August 8, 1972		
<b>Contractor:</b>	Shields Drilling Company, Inc. P. O. Box 709 Russell, Kansas		

Casing Record: 8-3/8" to 263', 5 1/2" to 3,394'

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1975  
09-25-1975

CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S LOG

0' - 15'	Top soil & clay
15' - 45'	Post rock
45' - 390'	Shale, sand, hard sand
390' - 489'	Hardsand & shale
489' - 849'	Shale, red bed
840' - 885'	Anhydrite
885' - 1455'	Shale
1455' - 1695'	Shale & lime streaks
1695' - 1865'	Shale & lime
1865' - 2025'	Lime & shale
2025' - 2165'	Lime & shale streaks
2165' - 2343'	Lime & shale
2343' - 2865'	Lime w/shale
2865' - 3291'	Lime
3291'	T. D.

STATE OF KANSAS     )  
                                  )SS  
County of Sedgwick    )

Arthur M. Scott, employee of owner and operator of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

Signature \_\_\_\_\_  
514 One Twenty Bldg., Wichita, Ks.

SUBSCRIBED AND SWORN to before me this 28th day of August, 1972

My commission expires March 22, 1975

\_\_\_\_\_  
Notary Public