

15-167-20558-00-00

R

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

OCT 21 1975  
10-21-1975  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Jet Drilling Co. Inc  
Complete Address 514 One-Twenty Bldg Wichita Ks 67202  
Lease Name Krug Well No. 2  
Location SESESE Sec. 23 Twp. 13 Rge. 14 (E) (W) X  
County Russell Total Depth 3290

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Nicholas Casing Pulling  
Address Box 373 Geneseo Kan 67444 License No. 711

Operation Completed: Hour 4<sup>00</sup> PM Day 17 Month 10 Year 1975

The above well was plugged as follows:

Sanded to 3250' @ 5sx Cement @ Dump Bailer  
Squeezed Thru 8 5/8" surface casing @ 25x Hulls  
25sx Mud Gel, 1sx Hulls @ 100 SX Cement  
Max Pressure - 400# Shut in Pressure - 250 #  
263' of 8 5/8" surface casing cemented @ 175 SX Cement  
3286' of 5 1/2" casing cemented @ 200 SX Cement  
No Perf. - open Hole Prod  
Recovered 1870' of 5 1/2" casing

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edward Rankin  
Well Plugging Supervisor

DATE 10/23-75

INV. NO. 2099-W