

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-187 21,733-00-00

Operator's Full Name Rains & Williamson Oil Company, Inc.

Complete Address 435 Page Court, 220 West Douglas, Wichita, Kansas 67202

Lease Name Speere Well No. 1

Location NE NW NE Sec. 23 Twp. 13 Rge. 14 ~~(East)~~ (West)

County Russell Total Depth 3278'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address _____ License No. _____

Operation Completed: Hour: 6:30 AM Day: 21 Month: June Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-250'-150 sacks 60-40 Poz. 2% 3%
Elev. 1816 GL

Hole circulated and filled with mud. 50 sacks cement pumped through
drill pipe at 620'. 30 sacks cement pumped through drill pipe at 260'.

Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and
hole cemented to base of cellar with 10 sacks cement. Rathole cemented
with 10 sacks cement. Cement used: 50-50 Pozmix w/4% gel and 3% CC

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1981

06-23-1981
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 7-27-81

INV. NO. 6095-W