

15-167-04351-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW NW SW

SEC. 23 TWP. 13 RGE. 14

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 4 Lease Dumler

Operator Mai Drg Co Address Russell, Kans

Field \_\_\_\_\_ County Russell

Total Depth 3327 Feet.

(Describe briefly the manner in which the well was plugged)

5 1/2" at 3285' with 100 sax cement behind - all other pipe pulled.

Baker plugs to 3260', top perforations at 3250'.

Filled with chat to 3220', set 4 sax cement with dump bailer,

pulled 2700' 5 1/2", filled hole with mud to 200', set rock and

25 sax cement, mud to 25', set rock and 10 sax cement to

bottom cellar.

**PLUGGING**  
FILE SEC 23 T 13 R 14  
BOOK PAGE 14 LINE 4

02-01-1952

*Edson Terry*  
District Conservation Agent

Date 1-29-52