

15-167-01926-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. 69-25LOCATION SW-SW-SWSEC. 23 TWP. 13 RGE. 14W

Dry Hole _____ Abandoned Oil Well *** Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease DumlerOperator Louis M. Mai Address Russell, Kansas.Field _____ County RussellTotal Depth 3285' Feet. P.B.TD. 2740'Plugging Contractor Barnes & Sons Pipe Pulling Co.Plugging Contractor's License No. 9Address Russell, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe - 8 5/8" @ 187' c.w.c. 5 1/2" set @ 3280' cem. 100 sx.Perforated from 2706' to 2710'. Sand back to 2696' and 5 sx. cem. with
dump bailer. Shot 5 1/2" off @ 2590' and pulled same.Squeezed with 20 sx. jell mud H.O.W.C.O. plug and 90 sx. cem. to base
of cellar.Halliburton Oil Well Cem. Co. did the job.

Milton G. G. G.
 District Conservation Agent

Date 7-4-56

RECEIVED
 JUL 6 - 1956
 CONSERVATION DIVISION
 WICHITA, KANSAS

PLUGGING

FILE SEC. 23 T. 13 R. 14WBOOK PAGE 69 LINE 25