

4-041630

11-25

15-051-02138-00-00
API number: 15- - 9-13-54

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW /4 SEC. 11 , 11 S, 17 W
990 feet from S section line
1650 feet from W section line
NGECC

Operator license# 30742

Lease McCombs well # 2

Operator: Palomino Petroleum, Inc.

County Ellis

Address: 4924 SE 84th. Street
Newton, Kansas 67114-8827

Well total depth 3370 feet ^{109.53}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1031 feet
w/500 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00A.M. Day: 25 Month: November Year: 94

Plugging proposal received from: John Lowry

Company: Palomino Petroleum, Inc. Phone:

Were: 5 1/2" casing set @ 3370' w/100 sxs. cmt. Perf. @ 2939' - 3362'.
Ordered 265 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 4:00P.M., Day: 25, Month: November, Year: 94

Actual plugging report: Sand bottom to 2900' w/5 sxs. cement on sand.
Shot casing at 1800'. Pumped 150 sxs. cement with 300# hulls. Pulled
to 1100' - spotted 25 sxs. cement. Pulled to 650' - spotted 65 sxs.
cement to circulate at surface. Pulled casing and filled to surface
with 10 sxs. cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Checked cement top.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did did not observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED

DATE

12-7-94

WV#

41831