

4-031697

15-051-02097-00-00
5-20
247
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1948

NW NE NE /4 SEC. 07, 11 S, 17 W
4950 feet from S section line
990 feet from E section line

Operator license# 30606

Lease Henderson well # 1

Operator: Murfin Drilling Co. Inc.

County Ellis

Address: 250 N. Water
#300
Wichita, Kansas 67202

Well total depth 3431 feet 111.50
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1132 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Co. Inc. License# 30606

Address: Hill City, Kansas

Company to plug at: Hour: A.M. Day: 20 Month: May Year: 92

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Co. Inc. Phone:

Were: Order 500 sx. 65/35 pozmix - 10% gel. - 500# hulls.
B.J. Services.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 20, Month: May, Year: 92

Actual plugging report: 8 5/8 set @ 1132' w/600 sx. cwc. 5 1/2" set @ 3430' w/100 sx. Squeezed 5 1/2" w/215 sx. cement blend with hulls mixed in to max. P.S.I. 900#. Close in P.S.I. 600#. Squeezed 8 5/8" with 75 sx. cement blend with hulls mixed in to max. P.S.I. 800#. Close in P.S.I. 450#. Plug complete.

Remarks: Alt. I completion from 1132'.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1879 GL

I did X / did not [] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1992
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 6-10-92
INV. NO. 35464