

15-051-02099-00-00
5-20

246
R

4- 031698

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1948

^{SE}
3300 ~~4620~~ E2 NE NE /4 SEC. 07, 11 S, 17 W
feet from S section line ANS KCC
330 feet from E section line

Operator license# 30606 Lease Henderson well # 3

Operator: Murfin Drilling Co. Inc. County Ellis

Address: 250 N. Water Well total depth 3408 feet ^{110.76}
#300 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 1108 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Co. Inc. License# 30606

Address: Hill City, Kansas

Company to plug at: Hour: A.M. Day: 20 Month: May Year: 92

Plugging proposal received from: John Gerstner

Company: Murfin Drilling Co. Inc. Phone:

Were: 8 5/8" set @ 1108' w/575 sx. cwc. 5 1/2" set @ 3407' w/100 sx.
O.H. 3405' - 07'. Order 500 sx. 65/35 pozmix - 10% gel. - 500# hulls.
B.J. Services. Packer stuck in hole. Backed off tubing. Circulated
5 1/2" full of cement through tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3:30P.M., Day: 20, Month: May, Year: 92

Actual plugging report: Spot cement blend slurry to surface from 3290'
through tubing. Squeezed 5 1/2" with total 195 sx. To max. P.S.I.
600#. Close in P.S.I. 500#. Squeezed 8 5/8" with 30 sx. to max.
P.S.I. 900#. Close in P.S.I. 500#. Plug complete.

Remarks: Alt. I completion from 1108'.

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO

Bottom plug(in place):YES X, CALC , NO Dakota plug:YES X, NO

Plugged through TUBING X, CASING . Elevation: 1879 GL

I did[X] / did not[] observe the plugging.

Carl Goodrow

(agent)

INVOICED
DATE 6-10-92
NO. 35462

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1992
CONSERVATION DIVISION
Wichita, Kansas
06-0392