

12-6 268 R

To: 6 062020  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-05688-00-00  
SE \_\_\_\_\_, SEC. \_\_\_\_\_, T 11 S, R 17 WXX

TECHNICIAN'S PLUGGING REPORT  
Operator License # 3613

2310 feet from S section line  
2310 feet from E section line

Operator: Quinoco Petroleum Co.  
Name & Address: Box 378111  
Denver, Co. 80237

Lease Name R. Stein Well # 1  
County Ellis 111.70

Well Total Depth 3437 feet

Conductor Pipe: Size 15 1/2 feet 69' w/65sks

Surface Casing: Size 10 feet 1161' w/450

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number 5278

Address Box 579 Great Bend, Ks. 67530

Company to plug at: Hour: 8:00AM Day: 6 Month: Dec Year: 19 89

Plugging proposal received from Aven Weaverling

(company name) Quinoco Pet. Co. (phone) 913-628-3989

were: Order 325 sks 60/40 poz 8% gel 23 sks gel, 5 sks hulls.

Ran tubing to 2600'.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30AM Day: 6 Month: Dec Year: 19 89

ACTUAL PLUGGING REPORT 10" set at 1161' w/450 sks. 7" set at 3447' w/150 sks.  
Open hole 3'. Pumped in 2" tubing. Ran 2" tubing to 2600'. Pumped 150 sks 60/40 poz

Pulled tubing to 1600' and circulated cement to surface w/200 sks cement w/300 psi.

10" 50 sks cement w/500 psi. RECEIVED  
STATE CORPORATION COMMISSION  
JAN 3 1990  
01-03-90

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: By Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-22-90

Signed [Signature] Gilbert G. Scheck

INV. NO. 27033  
12-6

FEB 09 1990

APR 10 1990

FORM CP-2/3  
Rev. 01-84