

6 060471

API NUMBER 15- 051-22-837-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 8, T. 11 S, R. 17 W
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5140
Operator: Frontier Oil Co
Name & Address: K.S. B.B.
Wichita, Ks.
67202

Lease Name Ganung Well #1
County Ellis 117.72
Well Total Depth 3622 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1129

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 176, Chase, Ks 67524

Company to plug at: Hour: 9:00AM Day: 13 Month: Feb Year: 19 85

Plugging proposal received from Millard Kelso
(company name) Kelso Casing (phone) 316-938-2457

were: Order 165 sh 8 5/8 posmix - 6 1/2 sh. Gel - 3 3/4 sh. G., 20 sh. Gel., 5 sh. hulls & 8 5/8" plug.

Plugging Proposal Received by John G. Schel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:20AM Day: 13 Month: Feb. Year: 19 85

ACTUAL PLUGGING REPORT 8 5/8" - 1129' w/ 450 sh. 5 1/2" at 3620' w/ 1250 sh.

Top perf. 3340'. Plugged bottom w/ 5 sh cement, sand & 5 sh cement to 3300'. Shot pipe 2 times & recovered 2331'. Pumped in 8 5/8" - 4 sh hulls, 25 sh. cement, 15 sh. Gel., 70 sh cement, 5 sh. Gel., 1 sh. hulls, reacidating & followed w/ 70 sh cement w/ 900 sh. cement

FEB 25 1985

Remarks: By Allid
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

I (did / did not) observe this plugging.

Signed John G. Schel
(TECHNICIAN)

2-22-85
64

DATE 2-26-85
FILE NO. 7136