

4-041481

7-27 15-051-30262-00-01

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- <sup>D-21, 182</sup> - OWWO

N2 NW NE /4 SEC. 08, 11 S, 17 W  
4950 feet from S section line  
1980 feet from E section line

Operator license# 5140

Lease Gilbert/Ganoung 2 well # 2

Operator: Frontier Oil Company

County Ellis

Address: 125 N. Market  
Suite 1720  
Wichita, Kansas 67202

Well total depth 3650 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 210 feet  
w/200 sx. <sup>118.62</sup>

Aband. oil well     , Gas well     , Input well X, SWD X, D & A     

Plugging contractor: Allied Cementing <sup>AUB ICC</sup> License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 12:00P.M Day: 27 Month: July Year: 93

Plugging proposal received from: Dick Parker

Company: Frontier Oil Company Phone: -

Were: 5 1/2" casing set @ 3636' w/250 sxs. cement. Perf. @ 3524'-3562'. p.v. @  
Anhy. 1156' w/450 sxs. cement. W.L.M. 3550'.  
Ordered 300 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[      ], Part[ X ], None[      ]

Completed: Hour: 1:30P.M., Day: 27, Month: July, Year: 93

Actual plugging report: Hooked-up to 5 1/2" casing. Pumped in 200 sxs.  
60/40 pozmix - 10% gel. w/300# hulls. Max. 1000# P.S.I. 700# S.I.  
Hooked-up to 8 5/8" S.P. Pumped in 50 sxs. 60/40 pozmix - 10% gel.  
with 1/4# F.C. Max. 300# P.S.I. 200# S.I.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks:

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO      AUG 2 1993

Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING X. Elevation: 1882 GL

I did X observe the plugging.

Dennis L. Hamel

(agent)

Form CP-2/3

INVOICED  
AUG 04 1993  
DATE                       
INV. NO. 38253