

4-070169

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-23,222-~~0000~~

NE NE SE /4 SEC. 09, 11 S, 17 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 8914

4/26

Lease: Simpson Well # 2

Operator: H&C Oil Operating  
401 N. Broadway  
Address: P.O. Box 86  
Plainville, Kansas 67663-0086

County: Ellis 118.63

Well total depth 3650 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 8 5/8 Inch @ 1049 feet  
W/425 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Golden Oil Company License# 30970

Address: 2905 Barclay - P.O. Box 861 - Hays, Kansas 67601-0861

Company to plug at: Hour: 9:00 A.M. Day: 26 Month: April Year: 2000

Plugging proposal received from: Ron Geist

Company: Golden Oil Company Phone: 785-628-1099

Were: 5 1/2" casing set at 3636' with 200 sxs.  
Ordered out 240 sxs 60/40 pozmix - 10% gel with 400# hulls.  
Perforations 3310' - 3348'.  
PBT.D. Sanded back to 2500' with 5 sxs plug.

Plugging Proposal Received by: Rich Williams  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 11:00 A.M. Day: 26, Month: April, Year: 2000

Actual plugging report: Golden Oil sanded back to 2500' with 5 sxs cement on top. Shot casing off at 2260'. Pulled 17 joints 5 1/2" casing. Allied pumped 110 sxs 60/40 pozmix - 10% gel with 200# hulls. Pulled to 1075' - pumped 40 sxs with 100# hulls. Pulled 5 1/2" to 550' - pumped 40 sxs. Pulled to 150' - pumped 30 sxs. Cement circulated. Pulled rest of casing out - hole full.

Remarks:  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1800 GL

I did[  ] / did not[  ] observe the plugging.

INVOICED  
DATE 5/1/00  
UNIT NO. 061652

RECEIVED  
STATE CORPORATION COMMISSION (agent)  
Form CP-2/3

APR 28 2000

CONSERVATION DIVISION  
Wichita, Kansas

(R)