

4-041759

E-25,334

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

3-19

API Number: 15- -

SE SE NE /4 SEC. 09, 11 S, 17 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 5293

Lease: Simpson Well # D-4

Operator: Helmrich & Payne, Inc.

County: Ellis

Address: P.O. Box 558  
Garden City, Kansas 67846

Well total depth 3408 <sup>110.76</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 208 feet

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 19 Month: March Year: 1996

Plugging proposal received from: Lee Fellhoelter

Company: Helmrich & Payne, Inc. Phone: -

Were: 4 1/2" casing set at 3908' w/150 sxs cement. Perf. at 3324' - 3371'  
Ordered 200 sxs. 60/40 pozmix - 6% gel with 1/4# F.C. plus 500# hulls.  
Squeeze at 1050' with 150 sxs - out of hole at 650' - drilled to 1062'..

RECEIVED  
STATE CORPORATION COMMISSION  
03-27-96  
CONSERVATION DIVISION  
MAR 27 1996

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:50 A.M., Day: 19, Month: March, Year: 1996

Actual plugging report: R.I.H. with tubing to tag T.D. at 1062'. Pulled up to 1052'.  
Spotted 25 sxs cement. Pulled up to 650'. Spotted 80 sxs cement and 25 sxs cement with 300#  
hulls to circulate at surface. Pulled tubing and squeezed casing with 20 sxs cement and 100#  
hulls. Max. P.S.I. 200#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED

MAR 28 1996

DATE

CTV. NO. 45143