

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

Rec'd
06-29-1981

API Number 15-167 21,605-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Shields Oil Producers, Inc.

Complete Address Shields Bldg., Russell, Kansas 67665

Lease Name Niederther Well No. C-1

Location SW SW SW Sec. 9 Twp. 13 Rge. 15 (~~East~~) (West)

County Russell Total Depth 3280'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address _____ License No. _____

Operation Completed: Hour: 10:30 PM Day: 24 Month: June Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-250'-circ. Elev. 1842 An. 899-936'

Hole circulated and filled with mud. 50 sacks cement pumped through
drill pipe at 576'. 30 sacks cement pumped through drill pipe at 250'.
Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and
hole cemented to base of cellar with 10 sacks cement. Rathole cemented
with 10 sacks cement. Mousehole cemented with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: William J. Roman
Conservation Division Agent

DATE 7-22-81

INV. NO. 5937-W