

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21777-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name K & E Petroleum, Inc.

Complete Address 100 South Main, Suite #300, Wichita, Kansas 67202

Lease Name Jacobs Well No. #1

Location NW/SE/NE Sec. 12 Twp. 13 Rge. 15 (East) (West)

County Russell Total Depth 3260'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Ks. 67202 License No. _____

Operation Completed: Hour: 4:15PM. Day: 14th Month: Oct. Year: 19 81

Plugging Operations attended by Agent? All Part None X

The above well was plugged as follows:

8 5/8"-404' sp. cuc. w/300 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 780' w/70 sacks cement

2nd plug @ 390' w/40 sacks cement

3rd plug-solid bridge of bulls and plug @ 40' w/10 sacks cement.

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
10-19-1981
1077 10 11

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 11-19-81

WELL NO. 8374-W