

15-167-00383-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

Verbal

FILE NO. _____

LOCATION SE SE NW

SEC. 13 TWP. 13 RGE. 15

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Jellison

Operator Derby Oil Co Address Wichita, Kans

Field Atherton County Russell

Total Depth 3280' Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 813' circulated with cement, 4 1/2" 3279' 125 sax behind,

lane Wells plugs and cement to 3170', perf at 3062' (Chat to
3060', 5 sax cement at 3060') 4 1/2" knocked off at 2750',
(Heavy mud to 500', wood plug, rock bridge and 20 sax
cement, Heavy mud to 40', wood plug, rock bridge and 10 sax
cement)

RECEIVED

03-30-1949
MAR 30 1949

[Signature]
District Conservation Agent

Date 3 - 23 - 49

PLUGGING
FILE SEC 13 TWP 13 RGE 15
WELL NO. 1 DATE 3-23-49