

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21, 955-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name SHIELDS OIL PRODUCERS, INC.

Complete Address SHIELDS BLDG. RUSSELL, KANS. 67665

Lease Name NIEDENTHAL Well No. "C" #2

Location NE-SW-SW Sec. 9 Twp. 13 Rge. 15 (East)(West)

County RUSSELL Total Depth 3325 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor SHIELDS DRILLING, INC. (VERNON ZORN)

Address SHIELDS BLDG. RUSSELL, KANS. 67665 License No. _____

Operation Completed: Hour: 3:00 PM Day: 3RD Month: AUG. Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 275 FT SP. CASING w/ 160 ST COMMON QUICK SET - (BY ALLIED)
ORDERED 150 ST 50/50 Fozmix 4% GEL-3% CA-CL. + 8 5/8" PLUG.
SPOT WITH DRILL STEM- WITH HEAVY MUD BETWEEN ALL PLUGS.
1 ST Plug. @ 660 FT w/ 80 ST CMT.
2ND Plug. @ 300 FT w/ 40 ST CMT.
3RD Plug - ^{SOLID BRIDGE} HULL'S. PLUG. @ 40 FT TO 0 w/ 10 ST CMT.
10 ST IN RAT HOLE (CIRCUMATE)

CEMENTED BY ALLIED CMT.

Amount of Surface Casing: 275 FT.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Marion J. Smith
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
AUG 09 1982
09-09-1982
STATE CORPORATION COMMISSION
Conservation Division Agent
Wichita, Kansas

INVOICED
DATE 8-19-82
INV. NO. 950-W

RECEIVED
STATE CORPORATION COMMISSION
Conservation Division
Wichita, Kansas