

15-167-04390-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION ~~NE SW SW~~ NE SW NW

SEC. 35 TWP. 13 RGE. 14

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Dumler

Operator Louis Mai Address Russell, Kans

Field _____ County Russell

Total Depth 5305 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 201' circulated with cement.

Filled with heavy rotary mud to 200', set two Halliburton

plugs, 1/2 sack hulls and 15 sax cement run through drill

pipe, filled with heavy mud to 35', set Halliburton plug,

1/3 sack hulls and filled hole to bottom cellar with cement.

08-14-1950
AUG 14 1950

PLUGGING
FILE SEC 35 TWP 13 R 14
BOOK PAGE 21 LINE 15

J. P. [Signature]
District Conservation Agent

Date 8-11-50 8-11-50