

15-167-00444-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SW NW

SEC. 5 TWP. 13 RGE. 15 W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Tracey

Operator Stearns Drg Co Address Russell, Kans

Field _____ County Russell

Total Depth 3273 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3272' with
125 sax cement behind.

Rock and cement and cement squeeze ~~xxxxxx~~ job to 3005'

Perforated at 2990', filled with chat to 2980', set 4 sax
cement with dump bailer, pulled approx 2450' 5 1/2", filled hole
with mud to 185', set rock bridge and 15 sax cement, filled
with mud to 35', set rock bridge and 10 sax cement to bottom
cellar.

PLUGGING
FILE SEC 5 T 13 R 15 W
BOOK PAGE 43 LINE 7

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1950
CONSERVATION DIVISION
Wichita, Kansas
District Conservation Agent

Date 11-14-50