

15-167-04300-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NE NE

SEC. 35 TWP. 13 RGE. 14

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Fritzler

Operator Stearns Drg Co Address Russell, Kans

Field _____ County Russell

Total Depth 5270 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 207' circulated with cement - 7" at 5261', 65 sax behind.

Lane-Wells plugs to 5215', top perf at 2966'.

Filled with mud and chat to 2960', dumped 6 sax cement with

bailer, pulled 2466' of 7", filled hole with heavy mud to 200',

set wood plug, rock and 20 sax cement, heavy mud to 35', wood

plug, rock and 15 sax cement to bottom cellar.

[Signature]
District Conservation Agent

Date _____

11-19-49

PLUGGING
FILE SEC 35 T 13 R 14
BOOK PAGE 125 LINE 48

NOV 23 1949
11-23-1949
ST...
...