

15-167-05856-00-00

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 103-4 County: Russell

Location: NW SW NW Sec. 35 Twp. 13 Rge. 14W (E) (W)

Name of Field: _____ Total Depth: 3268

I have this date completed supervision of plugging of:

Lease Name: Dumler Well No. # 1

Operator's Full Name: Louis M. Mai Operations

Complete Address: Box 33, Russell, Kansas

Plugging Contractor: Barns Pipe Pulling Co.

Address: 1450 Maple, Russell, Kansas License No. # 9

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour _____ Day 30 Month July Year 1958

The above well was plugged as follows:

Sand back to 3255' & 5 sax cement with dump bailer. Shot pipe off,
pulled same. Circulated 45 sax mud @ 600'. Mud to 300'. Pumped 50 sax
cement in hole @ 300' with Halliburton pump truck. Mud to 15', set rock
bridge, & 10 sax cement, cementing to base of cellar.

Signed: Don Truman
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1958
08-06-1958

PLUGGING
FILE SEC 35 T. 13 R. 14W
BOOK PAGE 103 LINE 4