

15-1167-19348-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 142-32

LOCATION NW-NW-SW

SEC 35 TWP 13 RGE. 14W

Dry Hole          Abandoned Oil Well \*\*\* Abandoned Gas Well         

I have this date completed supervision of plugging of:

Well No. 1 Lease Peter Boxberger

Operator Morgenstern & Specter Address Box 661. Russell, Kansas.

Field          County Russell

Total Depth 3281' Feet.

Plugging Contractor Arnett Casing Pulling Company.

Plugging Contractor's License No. 265

Address Hoisington, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe - NONE.. 5 1/2" set @ 3273' cem. 35 sx. Sand back to 3260'  
and 5 sx. cem. with dump bailer. Shot 5 1/2" pipe off @ 3050' and pulled  
pipe up to 2000' from top, pumped in 30 sx. jell mud @ 800 pounds of  
pressure. Pulled pipe up to 1600' from top, & pumped in 20 sx. jell mud  
with pressure up to 400 pounds. Then pulled pipe up to 300' from top,  
pumped in 5 more sx. of jell mud and followed up with 50 sx. cem. for  
fresh water plug. Pulled pipe out and next day bailed fluid out and mud  
to 35' from top, set plug, rock bridge and 50 sx. cem. to base of cellar.

Globe Oil Well Cem.          **RECEIVED**  
STATE CORPORATION COMMISSION

Wilton Schubert  
District Conservation Agent

Date 2-27-57

**PLUGGING**  
FILE SEC 35T 13 R 14W  
BOOK PAGE 142 LINE 32

MAR 2 - 1957  
03-02-1957  
CONSERVATION DIVISION  
Wichita, Kansas