

State of Kansas



JOHN CARLIN Governor
 R. C. LOUX Chairman
 JANE T. ROY Commissioner
 PHILLIP R. DICK Commissioner
 CAROL J. LARSON Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 200 Colorado Derby Building
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To be filed by Plugging Agent)

Dear Sir:

Mr. Harold Maley of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: K & E Petroleum, Inc.

Complete Address: 100 South Main, Suite #300, Wichita, Ks. 67202

Lease Name: Jacobs Well No. #1

Location: NW/SE/NE Sec. 12 Twp. 13 Rge. 15 (E) W

County: Russell Total Depth: 3260'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Harold Maley was instructed to plug the well as follows:

8 5/8"-404' sp. cuc. w/300 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

- 1st plug @ 780' w/70 sacks cement
- 2nd plug @ 390' w/40 sacks cement
- 3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.
- 5 sacks of cement in rat hole.

STATE CORPORATION COMMISSION

Very truly yours,

J. P. J. [Signature]
 Conservation Division Agent

10-19-1981
 CONSERVATION DIVISION
 Wichita, Kansas