



15-1167-21605-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

June 24, 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name: Niederthel Well No. C-1

Location: SW SW SW Sec. 9 Twp. 13 Rge. 15 ~~(E)~~ (W)

County: Russell Total Depth: 3280'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Weiler was instructed to plug the well as follows:

8-5/8"-250'-Circ. Circulate hole and fill with mud. Pump 50 sacks
cement through drill pipe at 576'. Pump 30 sacks cement through drill
pipe at 250'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to
40' and cap hole with 10 sacks cement. Cement rathole with 10 sacks
cement. Cement mousehole with 10 sacks cement.

Elev. 1842 KB Anhydrite 859' to 936'.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1981
06-29-1981
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent