

State of Kansas



FORM CP-2

15-167-21753-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Wilbert Boese of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: Yost Oil Operations

Complete Address: P. O. Box 811, Russell, Kansas 67665

Lease Name: Brungardt Well No. #1

Location: SW/SW/SW Sec. 14 Twp. 13 Rge. 15 (E) (W)

County: Russell Total Depth: 3300

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Wilbert Boese was instructed to plug the well as follows:

8 5/8"-242' sp. cuc. w/165 sacks cement-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem-with heavy mud between all plugs.

1st plug @ 660' with 70 sacks cement

2nd plug @ 240' with 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement

5 sacks of cement in rat hole.

Very truly yours,

RECEIVED
STATE CORPORATION COMMISSION

Robert R. Schuch
Conservation Division Agent

SEP 17 1981

09-17-1981
CONSERVATION DIVISION
Wichita, Kansas