

15-167-21777-00-00 S.C.C.

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Russell SEC. 12 TWP. 13S RGE. 15W E/W  
Location as in quarters or footage from lines:  
NW SE NE


Lease Owner K & E Petroleum, Inc.  
Lease Name JACOBS Well No. 1  
Office Address 300 Hardage Center, 100 S. Main, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed October 14, 1981  
Application for plugging filed October 14, 1981  
Plugging commenced October 14, 1981  
Plugging completed October 14, 1981

Locate Well  
correctly on above  
Section Platt.

Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered.  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3260'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set 1st plug @ 780' with 70 sx.  
Set 2nd plug @ 390' with 40 sx.  
Set 3rd plug @ 40' Solid Bridge with 10 sx.  
5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1981  
10-22-1981  
CONSERVATION DIVISION  
Wichita, Kansas

Plug was down @ 4:15 p.m., 10/14/81


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 19 81

Elizabeth G. Terry  
Elizabeth G. Terry Notary Public  


My Commission expires: 7-13-85

3.c.c.

15467-21777-00-00

CONTRACTORS WELL LOG

OPERATOR: K & E Petroleum, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: JACOBS #1  
 LOCATION: NW SE NE, Sec. 12-13S-15W,  
 Russell County, Kansas  
 SPUD DATE: 10/07/81  
 COMPLETION DATE: 10/14/81

0	45	Post Rock
45	387	Sand & Shale
387	390	Pyrite
390	641	Shale
641	846	Shale & Sand
846	881	Anhydrite
881	1328	Shale
1328	2937	Shale & Lime
2937	3221	Lime
3221	3260	Dolomite
	3260	Rotary Total Depth

Spud @ 12:45 a.m., 10/07/81. Drilled 406' of a 12 1/4" hole. Ran 10 joints of 8 5/8" 20# casing set @ 404' RTD. Cemented with 300 sx. Common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 9:50 a.m., 10/07/81.

3260' TD. Set 1st plug @ 780' with 70 sx. Set 2nd plug @ 390' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 4% gel, 3% c.c. Plug was down @ 4:15 p.m., 10/14/81. State plugger Gilbert Scheck.

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

OCT 21 1981  
 10-22-1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the JACOBS #1, NW SE NE, Sec. 12-13S-15W, Russell County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 20th day of October, 1981.

Elizabeth G. Terry  
 Elizabeth G. Terry  
 NOTARY PUBLIC

my commission expires 7-13-85

