

15-167-21968-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Russell SEC. 13 TWP. 13S RGE. 15 E/W
 Location as in quarters or footage from lines:
SW NW NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner J.M. Resources, Inc.
 Lease Name Cassity Well No. 2
 Office Address 425 S. Cherry St., Ste. 500 Denver, CO 80222
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 9-25-82
 Application for plugging filed N/A
 Plugging commenced 10/07/83
 Plugging completed 10/10/83
 Reason for abandonment of well or producing formation Poor producer

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Lansing/Kansas City Depth to top 2987' bottom 3188' T.D. 3325'

Show depth and thickness of all ^{City} water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Lansing / Kansas City</u>	<u>oil</u>	<u>2987'</u>	<u>3188'</u>	<u>4 1/2" 9.5#</u>	<u>surface to 3312</u>	<u>2615'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Poured sand down hole & bridged off @ 1711' - Poured 4 sxs cement
Pumped 2 sxs hulls - 20 sxs gel
Pumped 50 sxs 50/50 poz mix 6% gel & 3% CaCl
Released plug & pumped 50 sxs 50/50 poz mix 6% gel & 3% CaCl
SI w/ 250 psi

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.M. Resources, Inc.

STATE OF COLORADO COUNTY OF DENVER, ss.
Ron Maggard (employee of ~~owner~~) or (~~owner~~ or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Ron Maggard
425 S. Cherry #500 Denver Co
 (Address) 80222

SUBSCRIBED AND SWORN TO before me this 16th day of Nov., 1983

My Commission expires: July 29, 1985

[Signature]
 Notary Public.

STATE CORPORATION COMMISSION

NOV 28 1983
 11-28-1983
 WICHITA, KANSAS

