

3 023535

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS

Name & BUFFALO IV FEE FUND

Address PLUGGING PROJECT

AB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE, INC. Lic. # 30670

Address: P.O. BOX 386, CAHANUTE KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 8 Month: 7 2009

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All Part None X

Operations Completed: Hour: 12:00P.M. Day: 8 Month: 7 2009

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 8"

ANNULUS TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED

FROM THE 8' SUFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. 197 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

Remarks: GPS NO. 12. THIS WAS NO. 10 ON THE LEASE MAP. (Well # (OLE 12) in
(If additional description is necessary, use BACK of this form.) Ab. Well Database)

I DID NOT observe this plugging.

Control # 20090003-026

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
JUL 17 2009

KANSAS CORPORATION COMMISSION