

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-091-19179-00-00
 Spot: NENWNW Sec 33 Twp 13 S Rng 23 E / W
5065 Feet from N / S Line of Section
4464 Feet from E / W Line of Section
 GPS: Lat: 38.883033 Long: 94.868433 Date: 8/27/08
 Lease Name: STORM Well #: OW-1
 County: Johnson Total Vertical Depth: 700 feet

Operator License No: 101
 Op Name: STATE OF KANSAS String PROD - Casing Size 2.000 Depth _____ Pulled _____ Comments _____
 Address 1: FEE FUND
 Address 2: _____
 City: CHANUTE
 State: KS Zip Code: 66720 - _____

Well Type: GAS - Natural Gas - Production UIC Docket No.: _____ Date/Time to Plug: 6/4/10 / 9:00 am
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
 Proposal Rcvd from: MIKE KEPLEY Company Name: KEPLEY WELL SERVICE LLC Phone: (620) 433-7196

Proposed
Plugging
Report:

PUMP WELL FULL OF CEMENT.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 6/4/10 / 1:00 pm KCC Agent: TAYLOR HERMAN

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
PULLED 20' OF 1" PIPE FROM INSIDE OF 2" CASING. RAN A REAMER DOWN TO 700' INSIDE OF 2" CASING. RAN DOWN WITH OPEN ENDED 1" PIPE AND HIT BOTTOM AT 700'. PERFORATED THE 2" CASING AT 650', 350', AND 150'. RAN 1" DOWN TO 700' AND PUMPED 110 SACKS OF CEMENT FROM 700' TO SURFACE. CUT-OFF AND BACKFILLED.				

RECEIVED

JUN 25 2010

KCC WICHITA

Remarks: CONTRACT #11782 CONTROL# 20100048-001

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue: Yes No

District: 03 Taylor C. Herman
(Technician)