

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-037-01503-00-00
SESENE Sec/Twp/Rge 29-28-22E
2783 feet from south section line
292 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS
Name & FEE FUND
Address _____
AB oil well XXX Gas Well _____ SWD Well/ Input Well _____

Lease/Well# Coester 1 (COE-01)
County Crawford
Well Total Depth 397 feet
Production Pipe: 2 Size Feet _____
Surface Casing: 7 Size Feet _____
D & A

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 33749

Address: 19245 FORD ROAD CHANUTE, KS. 66720

Company to plug at: Hour: _____ Day: 10 Month: 8 2010

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERVICE Phone: 620-431-9212

Were: CLEAN OUT OLD WELL AND CIRCULATE CEMENT

Plugging Proposal Received by: Russell Hine

Plugging attended by Agent: All _____ Part XXX TECHNICIAN None _____

Operations Completed: Hour: _____ Day: 10 Month: 8 2010

Actual Plugging Report: Washed / ran 1" cement string to 397' inside of 2" and 275' on outside

Pumped 5bbl of cement inside. Circulated cement on backside. Pulled 1" from backside. Pumped cement to surface in 2". Pulled 200' x1" from inside and circulated cement again. Pulled all of 1" and topped off.

RECEIVED

104 SACKS OF PORTLAND USED AS REPORTED BY CONTRACTOR

SEP 10 2010

KCC WICHITA

Remarks: Control # 20100052-001

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:



Russell Hine P.I.R.T. II

TECHNICIAN
DIST # 3