

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19902-00-00

SW SE SW Sec/Twp/Rge 6-28-16E

222 (gps) feet from south section line

3708 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# Gallon, John #GAL01 (gps)

County Wilson

Operator: State Of Kansas Fee Fund

Well Total Depth 1545 feet

Name & John Gallon Lease Project

Production Pipe: NA Size Feet NA

Address _____

Surface Casing: 12 Size Feet NA

AB oil well _____ Gas Well XXXXXX

SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K W Oil Well Service, Inc

Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: _____ Hour: _____ Day: 17 Month: 5 2010

Plugging proposal received from: _____

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement.

Plugging Proposal Received by: _____

Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 17 Month: 5 2010

Actual Plugging Report: 10' of 14" surface pipe was set. Used drill rig to reach 800' where the bit

hit iron. The drill pipe was removed. A 1" cement string was lowered to 800' and the well pumped full of

cement from btm to top thru this cement string. A total of 475 sacks of portland cement were used to plug

well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: Control #20100070-001

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: _____

TECHNICIAN