

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205- 19903-00-00
SE NW SW Sec/Twp/Rge 6-28-16E
1705 (gps) feet from south section line
3962 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# Gallon, John #GAL02 (gps)County WilsonOperator: State Of Kansas Fee FundWell Total Depth 1545 (est) feetName & John Gallon Lease ProjectProduction Pipe: NA Size Feet NA

Address _____

Surface Casing: NA Size Feet NAAB oil well _____ Gas Well XXXXXX

SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K W Oil Well Service, Inc Lic. # 3097Address: 19450 Ford Road, Chanute, Kansas 66720Company to plug at: _____ Hour: _____ Day: 21 Month: 5 2010

Plugging proposal received from: _____

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement.Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXXOperations Completed: Hour: _____ Day: 21 Month: 5 2010

Actual Plugging Report: This well had no surface pipe so 30' of 12" surface pipe was set. The well was then drilled to 800'. The drill pipe was removed and a 1" cement string lowered to 800'. The well was pumped full of cement from btm to top thru this cement string. A total of 377 sacks of portland cement were used to plug the well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 02 2010

Remarks: Control #20100070-002

CONSERVATION DIVISION
WICHITA, KS

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN