

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-205-19904-00-00  
SE NE SE Sec/Twp/Rge 14-27-15E  
1935 (GPS) feet from south section line  
318 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Milligan III Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Milligan #CLA 03 (GPS)  
County Wilson  
Well Total Depth 950 (est) feet  
Production Pipe: 2 Size Feet NA  
Surface Casing: 7 Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 5 Month: 5 2010

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part XXXXXX None \_\_\_\_\_  
TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 5 Month: 5 2010

Actual Plugging Report: A 1" cement string was lowered down the outside of the 2" production pipe to 840'. A 1" cement string was washed down the inside of the 2" production pipe to 925'. The well was pumped full of cement from btm to top thru these cement strings. The cement strings were pulled and the well topped off with cement. A total of 187 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 28 2010

Remarks: Control #20100078-001

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KS

I partially observed this plugging

Signed:

Alan M. Dunning  
TECHNICIAN