

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-205-19906-00-00  
NW SE SE Sec/Twp/Rge 14-27-15E  
1286 (GPS) feet from south section line  
1151 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Milligan III Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Milligan #CLA 100 (GPS)  
County Wilson  
Well Total Depth 850 (est) feet  
Production Pipe: NA Size Feet NA  
Surface Casing: 8 Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 6 Month: 5 2010

Plugging proposal received from: Jeff Friederich

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All XXXXXX Part \_\_\_\_\_ None \_\_\_\_\_  
TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 6 Month: 5 2010

Actual Plugging Report: Approx 5' down was a round wood "plug" 8" in diameter and approx 2' in length. It had a 1" pipe sticking thru it. This wood also had approx 3' of cement above it. This wood plug was removed. A 1" cement string was then washed to 448' where the pipe hit hard. The well was then pumped full of cement from btm to top thru this 1" cement string. A total of 155 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20100078-003  
(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 28 2010

CONSERVATION DIVISION  
WICHITA, KS