

Side TWO

OPERATOR Hutchison Oil Operations LEASE NAME Krug 'C' SEC 24 TWP 13S RGE 14 (W)
WELL NO 2

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run. Check if samples sent Geological Survey.				
			Anhydrite	844
			Topeka	2712
			Heebner	2940
			Toronto	2959
			Douglas	2972
			Lansing	2999
			Base Kansas City	3258
			Arbuckle	3292
			Rotary Total	3420
DST-1	3252	3302		
Open: I.F. 45" F.E. 45"				
Blow: Weak, decreasing.				
Recovery: 70' of mud				
Pressures: ISP 600 psi FSIP 549 psi IFP 114-93 psi FFP 124-82 psi HSH 1819-1758 psi				
If additional space is needed use Page 2				

Report of all strings set — surface, intermediate, production, etc. **CASING RECORD (New) or (Used)**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		261'	Common	170	3% CC, 2% Gel
Production	7 7/8"	4 1/2"		3340'	Surfill		

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Estimated Production-I.P.	Oil bbls. MCF	Water % bbls. CFPB
Disposition of gas (vented, used on lease or sold)		Perforations

JAY HUTCHISON OIL OPERATIONS
JOLLY J, INC.
OIL FIELD DEALS
P.O. Box 572
RUSSELL, KANSAS 67665

May 14, 1984

Mr. Tom Leiker
State Corporation Commission
Conservation Division
200 Colorado Derby Building
202 West 1st Street
Wichita, KS 67202-1288

RE: Krug C #2, 24-13-14W, Russell County, Kansas

Dear Mr. Leiker

This letter is to advise you that the Affidavit of Completion Form filed on the above lease was filed in error.

Type of Completion should have read Temporarily Abandoned, instead of Dry. Pipe was set on this well and we intend to do further work on this well.

Please contact our office if you have any questions.

Sincerely

Dorothy Mashburn

Dorothy Mashburn, Office Manager

Enclosures

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1984

CONSERVATION DIVISION
Wichita, Kansas