

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Vern Zorn of Sheilds Drilling Co. Inc. has this  
date requested permission to plug the following described well:

Operator's Full Name: V. Frances Weigel

Complete Address: Z. Box 244 Gorham, Ks. 67640

Lease Name: Weigel F. Well No. 1

Location: SW NW NW Sec. 16 Twp. 13 Rge. 15 (E) (W)

County: Russell Total Depth: 3330'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A XXX

Other well as hereafter indicated:       

Mr. Vern Zorn was instructed to plug the well as follows:

8 5/8" 691' S.P. cuc. W/ 350 sacks common 2% Gel-3% Cal.Cl.

Ordered 135 sacks 50/50 posmix 4% Gel-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem w/ heavy mud between all plugs.

1st plug @ 750' W/ 70 sacks cement

2nd plug @ 310' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks cement in rat hole, and 5 sacks cement in mouse hole.

Very truly yours,

STATE CORPORATION COMMISSION

01-187982

JAN 18 1982

CONSERVATION DIVISION

Conservation Division Agent

WICHITA, KANSAS